



DOORS - STANDARD CONSTRUCTION OPTIONS		Options & Notes	List Price
*Label (per leaf)	Remove and Install new metal label	Metal: ITS/WHI 3, 1-1/2, 1, 3/4 hr, 20 Min	\$58
	Doors over 7'2"	Metal: ITS/WHI 3, 1-1/2, 1, 3/4 hr	\$187
Glass Lights/Louwer (price per cutout)	Glass Lights/Louwer cutout only	GS, NS, VS for lights and louvers. No trim available on mods.	\$105
	Glass light/louwer cutout w/ channel reinf.	Specify cutout size and location.	\$194
	Full glass light cutout with channel reinf.	FGS lights. No trim available on mods. Specify cutout size and location.	\$300
Top or Bottom Caps	Screw-in		\$49
Astragal Prep	<p>Inactive leaf - Add Flush Bolt prep (top & bottom) to 86 edge door to support astragal. (not available on L16 Doors at this time)</p> <p>Included but not Attached: Z-astragal with ASA & Flush Bolt Preps</p>	<p>FB Locations on door edge: Bottom of door to Center FB- 12" for 6'8", 7'0" & 8'0" Top of door to Center FB -12" for 6'8" & 7'0" doors -24" for 8'0" doors</p>	\$283
Electric hardware preps	Power Transfer Frame Prep	<p>Von Duprin EPT2 and EPT10. Includes mortar box.</p> <p>DETEX (PT-5)</p>	\$168
	Electric Hinge Prep (per Hinge)	<p>Hole in center of 4 1/2" Stock hinge reinforcement L Doors: 1" hole SZ Doors: 3/4" hole</p>	\$30
	Door Position Switch Prep (not available on Lock side of inactive doors)	<p>Schlage Electronics 679-05HM 1" round</p> <p>Sentrol 1076/1078 Series concealed models for 1" and 3/4" round</p>	\$33
Mark numbers			No Charge

FRAMES - STANDARD CONSTRUCTION OPTIONS		Options & Notes	List Price
*Label (per jamb)	Remove and Install new label	Metal: ITS/WHI 3, 1-1/2, 3/4 hr, 20 Min	\$30
Welded 3-side frame (STOCK)	Continuous weld		\$202
	Face weld		\$113
Anchors (per anchor)	EMA -- Pierce & Dimple only	Standard Quantities: - Jamb thru 7'1" (4 per jamb) - Jamb over 7'1 thru 8'9" (5 per jamb) (price per anchor)	\$9
	EMA -- Pierce & Dimple w/ Loose Anchors		\$15
	EMA** Hat anchor -- P&D, welded-in w/ bolts		\$30
	EMA Tube & Strap -- P&D, welded-in w/ bolts		\$40
	Stud Wall -- weld-in (typically 3 per jamb)		Jamb: Weld-in wood/Steel stud, Wood strap, Recessed Z, Compression jamb Base: Fixed base, Weld-in Wood stud base
Closer Reinf.	Regular arm (RA), Parallel arm (PA), or Top Jamb (TJ)	14ga. Reinforcement plates	\$31
		12ga. Reinforcement plates	\$43
Mark numbers			No Charge
Strike Preps	RPD - Rim Panic Strike prep	14ga, 8-1/2" tall, 44-9/16" top of reinforcement to bottom of frame	\$31
	SVRPD (Surface Vertical Rod) prep	14ga, 14" long plate, welded to soffit of frame header	\$31
	ASA Strike Prep	Available on -Blank Jamb for non-standard hardware location - Strike jambs with additional ASA Strike (deadlock)	\$65
	Universal (reversible) Flush Bolt Strike prep.	Plaster guard not included on DW frames	\$71
Hinge Preps	14 gauge Continuous hinge reinforcement	Available on blank jambs only	\$132
	4 1/2" Universal Hinge Prep (per Hinge)	Available on blank jambs only	\$41
	5" Universal Hinge Prep (per Hinge)	Available on blank jambs only	\$51
Electric hardware preps	Power Transfer Frame Prep	Von Duprin EPT2 and EPT10. Includes mortar box.	\$141
		DETEX (PT-5)	
	Electric Hinge Prep (per Hinge)	1" hole in center of hinge reinforcement	\$57
	Electric Strikes	Von Duprin (4211, 4212, 5100, 6210, 6211, 6400) HES (1006 SERIES)	\$107
Door Position Switch (DPS) -round hole preps up to 1" in		Schlage (679-05HM, 679-05WD) Sentrol Industries (1076, 1078)	\$57

Notes:

- * Refer to TD Manual for all labeled approvals. The included WHI labels must be relabeled if requirements change based on modifications.
- ** Default Anchor if no choice is specified.