## Stock Frame & Door Modifications

DOORS - STANDARD CO	ONSTRUCTION OPTIONS	Options & Notes	List Price
*Label (per leaf)	Remove and Install new metal label	Metal: ITS/WHI 3, 1-1/2, 1, 3/4 hr, 20 Min	\$49
	Doors over 7'2"	Metal: ITS/WHI 3, 1-1/2, 1, 3/4 hr	\$199
Glass Lights/Louver (price per cutout)	Glass Lights/Louver cutout only	GS, NS, VS for lights and louvers. No trim	\$111
	Glass light/louver cutout w/ channel reinf.	available on mods.  Specify cutout size and location.	\$206
	Full glass light cutout with channel reinf.	FGS lights. No trim available on mods.  Specify cutout size and location.	\$318
Top or Bottom Caps	Screw-in		\$25
Astragal Prep	Inactive leaf - Add Flush Bolt prep (top & bottom) to 86 edge door to support astragal.  (not available on L16 Doors at this time)  Included but not Attached: Z-astragal with ASA & Flush Bolt Preps	FB Locations on door edge:  Bottom of door to Center FB- 12" for 6'8", 7'0" & 8'0"  Top of door to Center FB  -12" for 6'8" & 7'0" doors  -24" for 8'0" doors	\$291
Electric hardware preps	Power Transfer Frame Prep	Von Duprin EPT2 and EPT10. Includes mortar box.  DETEX (PT-5)	\$178
	Electric Hinge Prep (per Hinge)	Hole in center of 4 1/2" Stock hinge reinforcement L Doors: 1" hole SZ Doors: 3/4' hole	\$26
	Door Position Switch Prep (not available on Lock side of inactive doors)	Schlage Electronics 679-05HM 1" round Sentrol 1076/1078 Series concealed models for 1" and 3/4" round	\$35
Mark numbers			No Charge



## Stock Frame & Door Modifications

FRAMES - STANDARD	CONSTRUCTION OPTIONS	Options & Notes	List Price
*Label (per jamb)	Remove and Install new label	Metal: ITS/WHI 3, 1-1/2, 3/4 hr, 20 Min	\$29
Welded 3-side frame	Continuous weld		\$214
(STOCK)	Face weld		\$119
	EMA Pierce & Dimple only		\$10
Anchors (per anchor)	EMA Pierce & Dimple w/ Loose Anchors	- Jambs thru 7'1" (4 per jamb) - Jambs over 7'1 thru 8'9" (5 per jamb)	\$15.50
	EMA** Hat anchor P&D, welded-in w/ bolts		\$31
	EMA Tube & Strap P&D, welded-in w/ bolts	(price per ancher)	\$41
	Stud Wall weld-in (typically 3 per jamb)	Jamb: Weld-in wood/Steel stud, Wood strap, Recessed Z, Compression jamb  Base: Fixed base, Weld-in Wood stud	\$12
	Regular arm (RA), Parallel arm (PA), or Top Jamb (TJ)	14ga. Reinforcement plates	\$31
		14ga. Full Width Reinforcement plates	\$93
Closer Reinf.			\$44
		12ga. Full Width Reinforcement plates	\$132
Remov. Mullion	Removable Mullion (Reinf. only)	14ga. Reinforcement in Head	\$31
	Face Mounted (Reinf. Only)		\$31
Coordinator	Soffit Mounted (Reinf Only)		\$93
Mark numbers			No Charge
Strike Preps	RPD - Rim Panic Strike prep	14ga, 8-1/2" tall, 44-9/16" top of reinforcement to bottom of frame	\$31
	SVRPD (Surface Vertical Rod) prep (Reinf. only)	14ga, 14" long plate, welded to soffit of frame header	\$31
	ASA Strike Prep	Available on -Blank Jamb for non-standard hardware location - Strike jambs with additional ASA Strike (deadlock)	\$69
	Universal (reversible) Flush Bolt Strike prep.	-Blank Jamb for non-standard hardware location - Strike jambs with additional ASA Strike	\$73
	14 gauge Continuous hinge reinforcement	- Jambs over 7'1 thru 8'9" (5 per jamb)  (nrice per anchor)  Jamb: Weld-in wood/Steel stud, Wood strap, Recessed Z, Compression jamb  Base: Fixed base, Weld-in Wood stud  14ga. Reinforcement plates  14ga. Full Width Reinforcement plates  12ga. Reinforcement plates  14ga. Reinforcement in Head  14ga. Reinforcement in Head  14ga, 8-1/2" tall, 44-9/16" top of reinforcement to bottom of frame  14ga, 14" long plate, welded to soffit of frame header  Available on  -Blank Jamb for non-standard hardware location - Strike jambs with additional ASA Strike (deadlock)  Plaster guard not included on DW  Available on blank jambs only  Available on blank jambs only  Available on Top or All Hinges  Von Duprin EPT2 and EPT10. Includes mortar box.  DETEX (PT-5)  1" hole in center of hinge reinf.  Von Duprin (4211, 4212, 5100, 6210, 6211, 6400)  HES (1006 SERIES)  3" in Schlage (679-05HM, 679-05WD)	\$136
Hinge Preps	4 1/2" Universal Hinge Prep (per Hinge)		\$43
	5" Universal Hinge Prep (per Hinge)	Available on blank jambs only	\$55
	High Frequency Hinge Prep. (per Hinge)	Available on Top or All Hinges	\$27
Electric hardware preps	Power Transfer Frame Prep	box.	\$141
	Electric Hinge Prep (per Hinge)	1" hole in center of hinge reinf.	\$57
	Electric Strikes		\$104
	Door Position Switch (DPS) -round hole preps up to 1" i	Schlage (679-05HM, 679-05WD)	\$57

- Notes: 1. \* Refer to TD Manual for all labeled approvals. The included WHI labels must be relabeled if requirements change based on modifications.
  - 2. \*\* Default Anchor if no choice is specified.

## About Allegion

Allegion (NYSE: ALLE) is a global pioneer in seamless access, with leading brands like CISA®, Interflex®, LCN®, Schlage®, SimonsVoss® and Von Duprin®. Focusing on security around the door and adjacent areas, Allegion secures people and assets with a range of solutions for homes, businesses, schools and institutions.





©2025 Allegion ALL-25-010 Rev. 02/25